



# Houseboat Construction Comparison Worksheet

## Sailabration Houseboats

## Other(s)

<b>Twin Hull Construction</b>	Huge 42" Cylindrical pontoons W/Air tight Bulk-Heads Every 72"; .125", 5052 Marine Alloy (Salt Water Alloy Available)
<b>Roof Construction</b>	
Roof Joist	2X8
Upper Deck Material	3/4" AC Fir Plywood
Roof Coating	2 Layer Fiberglass (1.5OZ Mat), Two Layers Gelcoat
Insulation	R-19 Fiberglass
<b>Floor Sub-Structure</b>	All aluminum, extruded decking with 8" Joist system on 48" Centers
<b>Wall Construction</b>	
Insulated	3/8" Plywood, 1-1/2" Foam, 3/8 Plywood Laminated both sides w/ Fiberglass/gelcoat
Non-Insulated	3/4" Plywood Laminated both sides w/ Fiberglass/Gelcoat
<b>Interior Ceiling</b>	7'-6" Ceiling Height W/ Stretched Marine Vinyl Finish
<b>Interior Cabinetry</b>	All Wood Custom Residential Style Cabinets Plastic Laminate Counter Tops W/ Wood Substrate (Upper End Tops Available)
<b>Interior Wall Covering</b>	1/4" Real Wood Panels Various Species
<b>Handrails</b>	Fully Custom, 1" (1-1/4" OD), Schedule 40 Aluminum Pipe, TIG Welded. (1-5/8" Available)
<b>Customization</b>	Fully Customizable Floor plans, Features and Décor
<b>Options</b>	About anything you can think of!